

## Case Study

Department of Immigration & Citizenship

Nauru Detention Centre

ABCO Water Systems was contracted to manufacture and install a wastewater treatment plant on the island of Nauru. The treatment plant will consist of a sewage pump station, rising main, wastewater treatment plant, and effluent disposal. (Discharged at Class C quality).

Two sea containers were transported to Pearce Air Base with all goods packed for transport inside that was required of this project, they were then flown by the Royal Australian Air Force direct to Nauru along with the ABCO Installers.

On arrival to site both sea containers were transported to their final destination where they were unpacked and the installation process began. A fiberglass pump station 1800mm diameter by 2000mm deep was installed containing Two submersible pumps on guide rails for ease of recovery and each pump rated at 520 l/m at 6.5m head, a control panel which offers dual pump and alternating operation, this control panel indicated high level and individual pump failure.

One of the twenty (20) foot sea container housed the control panel and a pump room. Inside the pump room are a Mixer Pump (2.2kW), an Irrigation Pump (2.2kW) and a Decant Pump (2.2kW). The control room was fully insulated and fitted with a split system air conditioner.

Mechanical screening of all influent was provided by way of a 2mm mechanical bar screen with all screened matter discharged by chute to the bin below.

Two tanks were installed for the treatment process, a Continuous Aeration Tank and Decant Aeration Tank. The Continuous Aeration Tank was fitted with two 7.5kW aerators for continuous operation and the Decant Aeration Tank was fitted with two 7.5kW aerators for intermittent operation.

Treated effluent was stored within a third tank this was treated with Hypochlorite prior to discharge through poly rising main to the mined (gossan) area adjacent to the treatment plant.

This waste water treatment plant was ready to receive sewage in four days of the plant being delivered to site.



Andrew Brown & Company Pty Ltd t/a ABCO Water Systems ABN: 80 084 539 079

Postal Address: PO Box 1131, Kelmscott DC 6997 Western Australia

Phone: (08) 9399 1662 Fax: 0(8) 9399 7667 Email: [sales@abco.net.au](mailto:sales@abco.net.au)

Electrical Contractor EC11076

